



Slab on grade vapor barrier must have a proper overlap to correct penetrations...we are unable to correct the vapor barrier when the wood stake is directly adjacent the construction joint or slab box-out.

We need to make sure that we have at least 6" of material before the stake installation...and there are several ways to accomplish this:

