

**Make sure that the pipes which penetrate the roof has the proper height above the finish roof level – and always review when we do roof replacements:**



**Pipe was cut short because the roof insulation was not taken into account.**



**The Pipe should be about 12\" (IL Plumbing Code 089.1430a) or more above the finished elevation of the roof.**

**Take into account tapered insulation.**

**Also – Please review your roof to make sure that vent pipes are at least 15'-0\" away from any HVAC equipment.**

